BRUHAT BANGALORE MAHANAGARA PALIKE

BYATARAYANAPURA DIVISION

WORKSLIP RATE ANALYSIS

Name of Work:	**Augmentation of Water Supply Through Borewell, Network of Pipelines and Ground Water Recharge Facilities in various layouts in Ward No-05 and Ward No-06 Byatarayanapura Sub Division**
Estimate Amount:-	**Rs 420.00 LAKHS**
Name of Contractor:-	**M/s Rajalakshmi Rock Drillers, prop Sri. Nagasandra Shamanna Ramarao No.41, Rukmini nagara, Nagasandra post, Bengaluru-560073.**
Approved amount:-	**37905841.13**
Tender premium:-	**4.99% Above**

Sl No	Description.	Unit	Page	Item	Basic rate	Lift charges	Total	AW @ 6%	Total Rate	Add T.P (+)4.99%	Final Rate.
47	KSRB 7.9 : Providing and fixing M.S.grill work for windows and ventilators weighing 21kg/sqm using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM complete as per specifications. Specification No.KBS 7.12 (p.g No 34.item No 7.9)	Sqm	Pg No.34 of KPWD S.R 2018-19	7.90	95.00	0	95.00	5.7	100.70	5.02	105.72

Asst Engineer

ಸಹಾಯಕ ಅಭಿಯಂತರರು

ಬಿ.ಬಿ.ಎಂ.ಪಿ ಬ್ಯಾಟರಾಯನಪುರ ಉಪ ವಿಭಾಗ

Assistant Executive Engineer

ಬ್ಯಾಟರಾಯನಪುರ ಉಪ ವಿಭಾಗ

ಬಿ.ಬಿ.ಎಂ.ಪಿ, ಬೆಂಗಳೂರು

Executive Engineer

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು

ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ,

ಬೃ.ಬೆ.ಮ.ಪಾ. ಬೆಂಗಳೂರು.

ಮುಖ್ಯ ಅಭಿಯಂತರರು

ಯಲಹಂಕ ವಲಯ

ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

Scanned by CamScanner